

ACTIVITY SCHEDULE FOR 900 DIA HUME PIPE FOR COMMUNITY

SL	CODE	ITEM OF WORK	QTY	RATE	AMOUNT
1	EW0106	Excavation in foundation trenches for Hume pipe culvert, width <2.0m, area<10 sq.m in plain, depth >300mm including dressing & ramming, disposal of surplus soil/rock within 50m lead & 1.5m lift.	88.20	221.50	19,536.30
2	SM0072	Providing and laying Hand packed stone filling or soling with stones	1.35	1,793.96	2,421.85
3	SM0006	Providing & laying Random Rubble Masonry with hard stone in wall in C.M 1:5	6.75	5,032.75	33,971.06
4	EW0195	a) Filling of trenches, sides of foundations etc.in layers<1.5m using selected excavated earth/boulder, ramming etc. within lead 50 m & lift 1.5m.	15.00	111.32	1,669.80
5	DR0095	Providing & laying NP2 class R.C.C pipes, including collars, jointing in cement mortar 1:2 including testing of joints etc. complete. 900 mm dia	10.00	4,779.23	47,792.30
6	SM0006	Providing & laying Random Rubble Masonry in wing wall with hard stone in foundation in C.M 1:5	6	5,032.75	30,196.50
TOTAL					135,587.81

DETAILS OF MEASUREMENT

SL	CODE	ITEM OF WORK	NOS	L	H	W	QTY	UNIT
1	EW0106	Excavation in foundation trenches for Hume pipe culvert width <2.0m, area<10 sq.m in plain, depth >300mm including dressing & ramming, disposal of surplus soil/rock within 50m lead &	1	7	1.8	7	88.2	cum.m
2	SM0072	Providing and laying Hand packed stone filling or soling with stones	1	3	0.15	3	1.35	cum.m
3	SM0006	Providing & laying Random Rubble Masonry with hard stone in foundation in C.M 1:5	1				4.21	cum.m
4	DR0095	Providing & laying NP2 class R.C.C pipes, including collars, jointing in cement mortar 1:2 including testing of joints etc. complete.	4	2.5			10	m
5	EW0195	a) Filling of trenches, sides of foundations etc.in layers<1.5m using selected excavated earth/boulder, ramming etc. within lead 50 m & lift 1.5m.	1				15	cum.m
6	SM0006	Providing & laying Random Rubble Masonry in wing wall with hard stone in foundation in C.M 1:5	4	2	1.5	0.5	6	cum.m