Bill of Quantities (BoQ) Form

(Refer e-procurement tender.bt for details and quoting)

SL. NO	BSR CODE	DESCRIPTION	UNIT	QTY	RATE (NU)	AMOUNT
1	**Excavation (Manually)**					
a	EW0031	Earth work in excavation over areas, depth >300mm, width >1.5m, area >10 Sq.m on plan, including disposal of excavated earth within 50m lead and 1.5m lift & disposed soil to be neatly dressed – All Types of Soil	Cu.m	29.51		
2	**Stone Soling Filling and Edging**					
a	SM0072	Providing and laying Hand packed stone filling or soling with stones	Cu.m	35.10		
3	**Form Work**					
a	RC0108	Providing & fixing centering and shuttering (formwork) using Shuttering Plywood, including Timber frame and timber strutting, propping with complete form tie system etc. and removal of formwork - Foundations, Footings, all works upto Plinth Level, etc.	Sq.m	91.50		
4	**Plain Cement Concrete**					
a	NA	Providing and laying in position plain cement concrete in foot path with broom/brush-finished surface with smooth, rounded edges. excluding the cost of centering and shuttering - 1:1.5:3 (1 cement : 1.5 sand : 3 graded crushed rock 20 mm nominal size)	Cu.m	32.28		
5	**Reinforced Concrete – concreting items**					
a	RC0002	Providing & laying in position reinforced cement concrete excluding the cost of centering, shuttering and reinforcement - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 sand : 3 graded crushed rock 20 mm nominal size)	Cu.m	1.54		
6	**Steel Reinforcement**					
a	RC0083	Providing & fixing Thermo-Mechanically Treated reinforcement bar (Yield Strength 500 MPa) for R.C.C work including cutting, bending, binding and placing in position complete	Kg	91.35		

7	**Fabricated and Built-Up Sections**					
a	SW0022	Steel work welded, in built up sections, trusses, frame-works including cutting, hoisting, fixing and appl. priming coat of red lead paint - In Tubular sections	Kg	669.25		
b	SW0003	Steel work in single section including cutting, hoisting, fixing and applying priming coat of red lead paint - In Tees, angles and channels	Kg	70.70		
9	**Providing and applying finishing coats**					
a	PT0047	Synthetic enamel, for steel & wood work, two coats on new work	Sq.m	29.9		
		TOTAL AMOUNT (NU)				

Note:

- **Site Visit** - Site survey and assessment of the Toilet (Compulsory) before submission of the bid.
- Must submit/upload rates in the Bills of Quantities (BoQ) Form as well as quote the rates in the e-procurement system.
- The Contractor shall bear all costs for safety equipment, PPE and related measures and shall be fully responsible for complying with all **Occupational Health and Safety (OHS)** requirements.
- No site camp or accommodation shall be provided by the Employer**,** and the Contractor shall make their own arrangements at their own cost for site camp, accommodation and related facilities.

Sign and Seal of the Bidder