


འབྲུག་གི་དངུལ་ཁང་།



BANK OF BHUTAN

A  Company

Banker to the Nation since 1968

**REQUEST FOR PROPOSAL (RFP) FOR
RENOVATION, REVAMP WORKS FOR BRANCH OFFICE,
and STAFF QUARTER BUILDINGS.**

Tender No.: 000/BoB/Tender/2025/43

Date: 16th December 2025

OWNERSHIP OF THIS REQUEST FOR PROPOSAL (RFP)

The content of this RFP is copyright material of the Bank of Bhutan (BoB).

Table of Contents

1.	SCOPE OF WORKS.....	4
2.	CLARIFICATION OF THE BIDDING DOCUMENT.....	4
3.	DOCUMENTS COMPRISING THE BID	4
4.	BID PRICE	4
5.	BID VALIDITY	4
6.	BID SECURITY	5
7.	SUBMISSION OF BIDS	6
8.	SUBMISSION DEADLINE	6
9.	BID OPENING	6
10.	EVALUATION OF BID.....	6
11.	BANK OF BHUTAN’S RIGHT TO ACCEPT ANY BID, AND REJECT OR CANCEL ANY OR ALL BIDS	6
12.	QUANTITY VARIATION.....	7
13.	AWARD OF CONTRACT	7
14.	DELIVERY SCHEDULE.....	7
15.	PERFORMANCE SECURITY.....	7
16.	LIQUIDATED DAMAGE	8
17.	FORCE MAJEURE	8
18.	PAYMENT TERMS	8
19.	DEFECT LIABILITY PERIOD	8
21.	TERMINATION.....	9
22.	GOVERNING LAW	9
23.	DISPUTE RESOLUTION	9
24.	DUE DILIGENCES.....	9
25.	ANNEXURE I: BID SUBMISSION FORM	10
26.	ANNEXURE II: PRICE SCHEDULE - DETAILED BILLS OF QUANTITIES	10
	ANNEXURE I: BID SUBMISSION FORM.....	11
	ANNEXURE II: PRICE SCHEDULE (BILL OF QUANTITIES).....	13
1.	LOT 1-GOMTU BRANCH STAFF QUARTER BUILDING.....	13
2.	LOT 2-SAMTSE BRANCH OFFICE BUILDING CUM STAFF QUARTERERROR! BOOKMARK NOT DEFINED.	
3.	LOT 3-TRASHIYANGTSE BRANCH OFFICE.....	31
4.	LOT 4-TRASHIGANG BRANCH OFFICE.....	40
5.	LOT 5-SAMDRUP JONGKHAR BRANCH OFFICE	44
6.	LOT 6-MONGAR BRANCH OFFICE	51

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

NOTICE INVITING TENDER

Date: 16th December 2025

NIT No.: 000/BoB/Tender/2025/43

- **Purchaser Name:** Bank of Bhutan
- **Scope of Works:** Renovations and Revamp of BoB Branch Offices and Staff Quarters.

Information to bidders

The tender allows full flexibility for participation. Interested and eligible bidders may opt to quote for a **single lot**, **multiple lots**, or **all lots**, as appropriate. Each lot will be evaluated independently, and bidders may submit quotations for any combination of lots based on their capacity, expertise, and interest. The award of the project shall be Lot-wise.

Bidder shall quote all the items inside the lot, and the total quoted amount should be written/reflected in the tender.bt bid submission.

For example, five items inside the lot cost 10,000, 50,000, 20,000, 10,000, and 10,000. The lot cost shall be 100,000 (total of 5 items costs). So, this total amount should be written in the tender.bt bid submission lot I 100,000.

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

TERMS AND CONDITIONS OF RFP

1. Scope of Works

- 1.1. The scope of work is Internal Renovation and Revamp works (Civil works, Plumbing minor works & Electrical minor works) at Branch Office & Staff Quarter Building. The bidder(s) price quoted shall be as per the technical specification and the Bill of Quantity are as attached in **Annexure -II**.

2. Clarification of the bidding document

- 2.1. Further information can be obtained in writing from the Customer Relationship & Valuation Section **OR** email lhakpa.dorji2990@bob.bt and sangay.namgay2989@bob.bt not later than three calendar days before the date of the bid submission. Clarification received after the clarification deadline shall not be entertained.

3. Documents comprising the bid

- 3.1. The bid must be accompanied by the following document:
- i. Valid CDB & Trade license.
 - ii. Tax clearance.
 - iii. Bid Submission Form in Annexure I.
 - iv. Bill of Quantity in Annexure II.
 - v. Bid Security

Note: failure to submit any of these documents shall be considered as non-responsive bid and hence shall be rejected.

4. Bid Price

- 4.1. The quoted price shall be in Ngultrum. The quoted price shall be inclusive of taxes, duties, and other levies.
- 4.2. The final place of work is at Branch Office & Staff Quarter Buildings as follows:
- 4.2.1. Lot 1-Gomtu Branch Staff Quarter Building
 - 4.2.2. Lot 2-Samtse Branch office building cum staff quarter Building
 - 4.2.3. Lot 5-Trashiyangtse Branch office Building
 - 4.2.4. Lot 6-Trashigang Branch office Building
 - 4.2.5. Lot 7-Samdrup Jongkhar Branch office Building
 - 4.2.6. Lot 8- Mongar Branch office Building

5. Bid Validity

- 5.1. The bid shall be valid for **90 calendar days** from the date of submission of the bid. In

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

exceptional circumstances, prior to the expiration of the bid validity period, the Bank of Bhutan may solicit the Bidder's consent to an extension of the bid validity period. The request and responses shall be made in writing. A bid valid for a shorter period shall be considered non-responsive and shall be rejected.

6. Bid Security

- 6.1. The bid shall be accompanied by a bid security in the form of Cash Warrant/ Unconditional Bank Guarantee/Banker's Cheque /Demand draft in the name of the Manager, Respective Branch, issued by a reputable Financial Institution enforceable in any Banks in Bhutan as follows.

#	Branch Office	Bid Security
1	Gomtu Branch Staff Quarter Building	24,000.00
2	Samtse Branch office building cum staff quarter Building	10,000.00
3	Trashiyangtse Branch office Building	10,000.00
4	Trashigang Branch office Building	10,000.00
5	Samdrup Jongkhar Branch office Building	50,000.00
6	Mongar Branch office Building	26,000.00

The Bid security should be valid up to 90 days from the day of opening. The Bid Security is to be submitted as a part of the Bid. Any Bid not accompanied by bid security of adequate value and validity shall be rejected by Bank of Bhutan as non- responsive.

The bid security shall be forfeited in the following cases:

- a) If the Bidder withdraws the bid after Bid opening during the period of Bidvalidity;
- b) If the Bidder does not accept the correction of the Bid price;
- c) In the case of a successful bidder, if the bidder fails to sign the Contract or furnish Performance Security within the specified time limit.

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

7. Submission of Bids

The bidder(s) shall submit the bid online via tender.bt. The bid submitted in hard copy shall not be accepted.

8. Submission deadline

The deadline for receipt of your bid(s) and other required documents shall be as per clause 3 of the above. The bid submission timeline is ON or BEFORE 30th December 2025 at 1300 hours, Bhutan Standard Time (BST). Late submission of a bid(s) shall not be accepted.

9. Bid Opening

9.1 The bid(s) shall be opened in the presence of bidders or their representatives who choose to attend on 30th December 2025 at 1500 hours (BST).

In case the due date falls on non-working days, the opening of the bid shall be on the next working day at the same time.

10. Evaluation of Bid

a. Evaluation of the bid

- i. To assist in the examination, evaluation, and comparison of bids, the Bank of Bhutan may, at its discretion, ask the Bidder for a clarification of its Bid. All responses to requests for clarification shall be in writing, and no change in the price or substances of the Bid shall be sought, offered, or permitted. Failing to respond to the clarifications sought by the Bank of Bhutan within the specified time period shall be treated as non-responsive and hence be rejected.
- ii. Non-compliance with the technical/product specification shall be considered a non-responsive bid and shall not be evaluated.

b. While evaluating the quotations, the Bank will determine for each quotation and evaluate the price by adjusting the quoted price in case there are any arithmetical errors as follows:

- i. Where there is a discrepancy between the Unit Rate and the line item, the resulting figure from multiplying the Unit Rate by the quantity shall prevail unless, in the opinion of the Bank, there is an obvious gross misplacement of the decimal point in the Unit Rate; and
- ii. If the bidder refuses to accept the correction, this quotation will be rejected, and the bid security shall be forfeited.

11. Bank of Bhutan's Right to Accept Any Bid, and Reject or Cancel any or All Bids

11.1. The Bank of Bhutan is not bound to accept the lowest bid and reserves the right to accept, reject, or cancel any or all the bids without assigning any reason whatsoever.

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

12. Quantity Variation

- 12.1. Depending on the final requirement, at the time of the award of the Contract, the Bank of Bhutan may increase or decrease the quantities by twenty-five percent (25%) of the indicated quantity.

13. Award of Contract

- 13.1. The Bank of Bhutan shall award the contract to the bidder whose offer has been determined to be the lowest evaluated Bid. The Bank of Bhutan shall issue a Notification of Award/Letter of Acceptance to the successful bidder. Until a formal contract is prepared and executed, the notification of award shall constitute a binding contract.

14. Delivery Schedule

- 14.1. The execution of works and related services shall be completed within **90 calendar days** from the date of the work order.
- 14.2. The location of renovation & revamp works is at Bank of Bhutan, Branch Office & Staff Quarter Building as follows.

14.2.1 Lot 1-Gomtu Branch Staff Quarter Building

14.2.2 Lot 2-Samtse Branch office building cum staff quarter Building

14.2.3 Lot 3-Trashiyangtse Branch office Building

14.2.4 Lot 4-Trashigang Branch office Building

14.2.5 Lot 5-Samdrup Jongkhar Branch office Building

14.2.6 Lot 6- Mongar Branch office Building

- 14.3. The bidder's quoted completion schedule of works more than 60 days shall be considered as non-responsive.

15. Performance Security

- 15.1. The contractor shall be required to furnish performance security of 10% of the quoted amount in the form of cash warrant, demand draft or unconditional Bank Guarantee in the name **Chief Executive Officer, Bank of Bhutan Limited**, issued by a reputable financial institution enforceable in any Banks in Bhutan, which shall be furnished upon issuance of notification of the award. Performance Security shall be valid till the handing taking.
- 15.2. The 10% of the payment shall be retained as retention money till the issuance of No Defects Liability Certificate.
- 15.3. The performance security shall be forfeited in the following case if the bidders:
- i. Fails/withdraws to perform the contractual obligation under the Bank of Bhutan order/contract agreement.
 - ii. Fails to comply as per the specification/ inferior quality of works.

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

16 Liquidated Damage

16.1 If the Contractor fails to complete the work within the period specified in the contract ,the Bank of Bhutan shall deduct liquated damages at the rate of **0.3%** per day of the value of uncompleted items of work and shall be a maximum of **10%** of the total quoted price.

17 FORCE MAJEURE

- a) The contractor shall not be liable for forfeiture of its performance security, liquidated damages, or termination for default if and to the extent that it's delay in performance or other failures to perform its obligations under the Contract is the result of an event of Force Majeure.
- b) For purposes of this Clause, "Force Majeure" means an event or situation beyond the control of the Contractor that is not foreseeable, is unavoidable, and its origin is not due to negligence or lack of care on the part of the Contractor. Such events may include, but not be limited to, acts of the Purchaser in its sovereign capacity, wars or revolutions, fires, floods, epidemics, quarantine restrictions, and freight embargoes.
- c) If a Force Majeure situation arises, the Contractor shall promptly notify the Bank of Bhutan in writing of such condition and the cause thereof. Unless otherwise directed by the Bank of Bhutan in writing, the Contractor shall continue to perform its obligations under the Contract as far as it is reasonably practical and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.

18 Payment Terms

- 18.1 No advance payment shall be made prior to the completion of the work, and the payment will be made within 30 working days after submitting the Running Account Bills for the completed works. From the contract amount, only 90% shall be made after completion of the works and the remaining 10% shall be paid after the completion of the warranty period.
- 18.2 At the time of the release of payment, all applicable taxes such as Tax Deducted at Source [TDS] from the gross amount of bills as per the Income Tax Act of Bhutan shall be deducted.

19 Defect Liability Period

19.1 The defect liability period for works shall be for 6 months. If the Contractor fails to rectify and or replace the defective works within 30 days, the performance security shall be used to cover the cost of works not completed or defective works not replaced or rectified.

20 Submission of Bid

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

- 20.1 The Bidder shall submit the bid submission form using the form in Annexure I, and II. ***This form must be completed without any alterations to its content.*** All blank spaces shall be filled with the information requested.
- 20.2 A bid in which the bid submission form is not duly filled, signed, and sealed by the bidder shall be rejected.

21 Termination

- 21.1 The Bank of Bhutan may, by written notice, terminate the contract [if applicable] in whole or in part at any time for its convenience.
- 21.2 If the Contractor fails to fulfill any other terms and conditions specified in the contract, or exceeds the maximum amount of liquidated damages.
- 21.3 If the Contractor does not take any remedial action for the default within a given time period after notifying.

22 Governing Law

- 22.1 The contract shall be governed by and interpreted in accordance with the Laws of Bhutan.

23 Dispute Resolution

Any settlement of dispute or arbitration of matter arising from the contract shall be settled as per the Alternative Dispute Resolution Act of Bhutan 2013.

24 DUE DILIGENCES

The bid shall be deemed to have been submitted after careful study and examination of this RFP. The bid should be precise, complete, and in the prescribed format as per the requirement of this RFP document. Failure to furnish all information or submission of a bid not in line with this RFP will be at the bidders' risk and shall result in the rejection of the bid. Also, the grounds for rejection of the Bid should not be questioned after the final declaration of the successful Bidder.

The bidder is requested to carefully examine the RFP, and the terms and conditions specified therein and if there appears to be any ambiguity, contradictions, inconsistency, gap, and/or discrepancy in the RFP, the Bidder should seek necessary clarification.

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

25 Annexure I: Bid Submission Form

The bidders shall be required to submit their bids along with the duly completed Bid Submission Form. *For all Lots, a single general Bid Submission Form shall be submitted.*

26 Annexure II: Price Schedule - Detailed Bills of Quantities

- 26.1 Lot 1-Gomtu Branch Staff Quarter Building
- 26.2 Lot 2-Samtse Branch office building cum staff quarter Building
- 26.3 Lot 3-Trashiyangtse Branch office Building
- 26.4 Lot 4-Trashigang Branch office Building
- 26.5 Lot 5-Samdrup Jongkhar Branch office Building
- 26.6 Lot 6- Mongar Branch office Building

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

Annexure I: Bid Submission Form

[The Bidder shall fill in this form in accordance with the instructions indicated. No alterations to its format shall be permitted and no substitutions shall be accepted.]

Date: *[Insert date of Bid submission]*

Tender No.: *[Insert number]*

To: *[Insert complete name of the Bank of Bhutan]*

We, the undersigned, declare that:

(a) We have examined and have no reservations about the Bidding Documents, including Addenda number:..... ***[insert the number and date of issue of each addendum];***

(b) We offer to execute in conformity with the Bidding Documents and in accordance with the Scope of Work, the following Works and Related Services: ***[insert a brief description of the works and Related Services];***

(c) The total price of our Bid, excluding any discounts offered in the item is: ***[insert the Bid Price in words and figures, indicating the various amounts and their respective currencies];***

(d) The discounts offered and the methodologies for their application are:

Discounts. If our Bid is accepted, the following discounts shall apply: ***[Specify in detail each discount offered and the specific item of the Schedule of Works to which it applies.]***

Methodology of Application of Discounts. The discounts shall be applied using the following methodology: ***[Specify in detail the methodology that shall be used to apply the discounts];***

(e) Our Bid shall be valid for a period of ***[Insert number]*** from the date fixed for the Bid submission deadline and it shall remain binding upon us and may be accepted at any time before the expiry of that period.

(f) If our Bid is accepted, we commit to provide a Performance Security in accordance with Clause 15 for the due performance of the Contract.

(h) We, including any subcontractors for any part of the Contract, have nationality from eligible countries, viz: *[Insert the nationality of the Bidder, including that of all parties that comprise the Bidder if the Bidder is a JV/C, and the nationality of each subcontractor].*

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

- (i) We have no conflict of interest.
- (j) Our firm, its affiliates, or subsidiaries - including any subcontractors for any part of the contract - has not been declared ineligible by the Bank of Bhutan under the laws or official regulations of Bhutan.
- (k) We have read the terms and conditions carefully, understood, and agree to comply with all the clauses which are mentioned therein. In case of any breach of any condition on our part, we shall be liable for actions as per the terms and conditions of the Contract.
- (l) We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us until a formal contract is prepared and executed.
- (m) We understand that you are not bound to accept the lowest evaluated Bid or any other Bid that you may receive.
- n) We accept the Vendor Performance Management System.

Signed: _____ [insert signature of the person whose name and capacity are shown]

In the capacity of _____ [*insert legal capacity of the person signing the Bid Submission Form*]

Name: _____ [*insert complete name of the person signing the Bid Submission Form*]

Duly authorized to sign the bid for and on behalf of: _____ [*insert complete name of Bidder*]

Dated on _____ day of _____ [*insert date of signing*]

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

Annexure II: Price Schedule (Bill of Quantities)

1. Lot I: Gomtu Branch Staff Quarter Building *(Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).*

CODE NO.	ITEM NAME	QTY	UNIT	RATE	AMOUNT	REMARKS
A.	BLOCK TYPE -B1 (MANAGER QUARTER)					
	DISMANTLING & DEMOLITION WORK					
	Brick & Hollow Block Masonry					
	Demolishing brick work including stacking useful materials & disposal of rubbish within 50m lead					
DD0017	In cement mortar	0.75	cu.m			
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	13.00	each			
	Cisterns					
DD0100	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	1.00	no			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.11	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Panelled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	5.27	sq.m			
	Kicking plate					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	0.77	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	2.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
250mm	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	12.00	each			
	STEEL					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
	Doors / Windows & Accessories					
SW0045	Sliding, open, able, and pivoted windows	29.77	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

SW0056	5mm thick, plain glass	9.13	sq.m			
	ROOFING					
	C.G.I Sheeting					
	Providing & fixing Pre-Painted Galvalume (PPGL) sheeting, including necessary accessories for fixing sheet (excluding the cost of purlins, rafter and trusses) - 25g					
RF0004	25g (0.50mm)	6.72	sq.m			
	PLUMBING - INDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0300	15 mm nominal outer dia Pipes	5.00	m			
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	1.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

PI0205	15mm, standard vertical, c.p knob	2.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	1.00	each			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	297.56	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	297.56	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	297.56	sq.m			
	ELECTRICAL WORKS IN BUILDING					
	BOXES					
	PVC Boxes					
BX0021	2 Module	6.00	each			
	SWITCHES & SOCKETS					
	Supplying & fixing of socket outlet on existing PVC surface box including necessary cutting, connection testing etc. as required.					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

SS0151	5 pin universal socket outlet	7.00	each			
	Supplying & fixing of switch/socket on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0166	5/6 pin, 6/16A socket outlet, shuttered	12.00	each			
	Total cost of work code.no A (For 1-UNIT)					
B.	BLOCK TYPE -C1 (STAFF QUARTER-2 UNITS)					
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	9.00	each			
	Cisterns					
DD0100	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	1.00	no			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.11	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

WW0210	Class 'A' (conifer)	5.40	sq.m			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	0.90	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	3.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
WW0656	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	3.00	each			
	STEEL					
	Doors / Windows & Accessories					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
SW0045	Sliding, open, able, and pivoted window	40.75	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	aluminum frame & accessories)					
SW0056	5mm thick, plain glass	10.82	sq.m			
	PLUMBING - INDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0300	15 mm nominal outer dia Pipes	5.00	m			
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	1.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	2.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	1.00	each			
	PLASTERING					
	Putty finishes					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

PL0125	Providing & applying putty of thickness 2mm or more over plastered surface to prepare the surface even and smooth complete.	25.00	sq.m			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	223.60	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	223.60	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	223.60	sq.m			
	Cost of work for code no.B for 1-Unit					
	Total cost of work for code no.B for 2- Units					
C.	BLOCK TYPE D9 (STAFF QUARTER-4 UNITS)					
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	8.00	each			
	Cisterns					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

DD0100	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	1.00	no			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.19	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	8.14	sq.m			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	1.54	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	3.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
WW0656	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

WW0665	150mm	3.00	each			
	STEEL					
	Doors / Windows & Accessories					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
SW0045	Sliding, open, able, and pivoted windows	16.46	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					
SW0056	5mm thick, plain glass	3.86	sq.m			
	PLUMBING - INDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0300	15 mm nominal outer dia Pipes	10.00	m			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	1.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	2.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	1.00	each			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	190.02	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	190.02	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	190.02	sq.m			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Cost of work for code no C 1-Unit					
	Total cost for work for Code no.C for 4-Units					
	BLOCK TYPE E5 (STAFF QUARTER-2 UNITS)					
	DISMANTLING & DEMOLITION WORK					
	Brick & Hollow Block Masonry					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	3.00	each			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.11	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	4.91	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	3.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

WW0656	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	3.00	each			
	STEEL					
	Doors / Windows & Accessories					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
SW0045	Sliding, open, able, and pivoted windows	12.84	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					
SW0056	5mm thick, plain glass	1.70	sq.m			
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	84.50	sq.m			
	Painting Items					
	Providing & applying one coat of primers					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

PT0010	Cement primer	84.50	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	84.50	sq.m			
	INDOOR LUMINIARES					
	Surface Luminaire (Light Emitting Diode Source)					
	Supplying & fixing of prewired indoor surface/ceiling mounted round/square LED luminaires of 3000/4000/6000k, complete with all accessories with necessary testing & commissioning.					
IL0302	5W	2.00	each			
	Estimated cost for 1-UNIT					
	Total cost of works for code no.C for 2 UNITS					
Total cost of works (code no. A+B+C+D) in figures:				Nu.		
Total cost of work (code no. A+B+C+D) in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

2. Lot II: Samtse Branch office building cum staff quarter Building

(Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).

CODE NO.	ITEM NAME	QTY	UNIT	RATE	AMOUNT	REMARKS
A.	SAMTSE BRANCH OFFICE WITH STAFF QUARTER					
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	1.00	each			
	Cisterns					
DD0100	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	4.00	no			
	BRICK WORK					
	Half - Brick Masonry (125mm)					
	Providing & laying Second-Class Half-brick Masonry (125 mm) in superstructure below floor 2 level					
BW0021	In cement mortar 1:4	5.10	sq.m			
	STEEL					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
	Doors / Windows & Accessories					
SW0045	Sliding, open, able, and pivoted windows	3.51	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					
SW0056	5mm thick, plain glass	2.18	sq.m			

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	TILING - WALL & FLOOR				
GL0001	Providing and fixing vitrified tiles in skirting, step risers, dado and wall in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, on 12 mm thick cement mortar 1:3 (1 cement:3 sand) finished with Tiles grout flush-pointing	0.5	sq.m		
GL0002	Providing and laying vitrified tiles in flooring, treads of steps and landings in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) finished with tiles grout flush pointing	6.00	sq.m		
	PLUMBING - INDOOR WORK				
	CPVC Pipe				
	Pans & Cisterns				
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete				
PI0050	white, with plastic seat & lid	1.00	each		
	PLASTERING				
	Cement Plaster				
	Providing & laying 12mm cement plaster				
PL0021	C.M 1:4	10.20	sq.m		
	PAINTING & WALLPAPER				
	Surface Preparation				
	Surface preparation removing by scraping, sand papering, including scratch repairs				
PT0001	White colour-wash	1,100.01	sq.m		
	Painting Items				
	Providing & applying one coat of primers				
PT0010	Cement primer	1,100.01	sq.m		

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	1,100.01	sq.m			
	ELECTRICAL WORKS IN BUILDING					
	FANS					
	Supplying, installation, testing & commissioning of ceiling fan 240-volt A.C 1400 rpm with all accessories such as down rod, sweep 3 Nos., canopy 2 Nos., condenser and fan body etc. complete as required					
FN0002	1200mm sweep	2.00	each			
	ENTRANCE GATE PAINT					
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0002	Dry oil bound distemper	8.82	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0011	Metal work - synthetic red oxide prime	8.82	sq.m			
	Providing and applying finishing coats					
PT0048	High gloss synthetic enamel/for steel & woodwork, two coats on new work	8.82	sq.m			
	Total cost of code.no A works					
B.	ATM SHED NEAR SAMTSE BRANCH					
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

		18.86	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	18.86	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	18.86	sq.m			
	Total cost of code.no B works					
C.	ATM SHED NEAR SAMTSE DZONGKHAG ADMINISTRATION					
	DISMANTLING & DEMOLITION WORK					
	Ceiling & Cladding					
DD0065	Dismantling cement A.C, celotex, hardboard ceiling, partition, including stacking useful materials & disposal rubbish within 50m	9.43	sq.m			
	Particle Board					
	Providing & fixing Pre-laminated Particle Board Lining with necessary nails etc. complete (excluding cost of frame)					
WW0111	10 mm	9.43	sq.m			
	Total cost of code no.C works					
Total cost of works code.no A+B+C in figures:				Nu.		
Total cost of work code.no A+B+C in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

3. Lot III: Trashiyangtse Branch Office *(Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).*

CODE NO.	ITEM NAME	QTY	UNIT	RATE	AMOUNT	REMARKS
	NEW TOILET CONSTRUCTION WORKS					
	BRICK WORK					
	One - Brick Masonry (250mm)					
	Providing & laying Second-Class Brick work in Foundation & Plinth					
BW0002	In cement mortar 1:4	2.81	cu.m			
	Woodwork					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.03	cu.m			
	Undressed Timber Framing					
	Providing & fixing roof framing, in trusses, purlins, rafters, posts, post plates including hoisting, etc. (excluding steel items)					
WW0061	Class 'A' (conifer)	0.05	cu.m			
	Wall and ceiling Linings					
	Plywood					
	Providing & fixing Plywood lining with necessary nails etc. including complete beading (excluding cost of frame)					
WW0132	6 mm, commercial	2.50	sq.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	2.50	sq.m			
	Shutters Fittings					
	Providing & fixing anodized aluminum tower bolt (barrel type) with aluminum screws etc. complete					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

WW0590	200mm	1.00	each			
	Providing & fixing anodized aluminum sliding door bolts with nuts and aluminum screws etc. complete					
WW0602	200mm	2.00	each			
	Providing & fixing anodized aluminum handles with necessary aluminum screws etc. complete					
WW0610	150mm	2.00	each			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	0.80	sq.m			
	STEEL					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)					
SW0045	Sliding, open, able, and pivoted windows	2.22	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					
SW0057	5mm thick frosted glass	0.45	sq.m			
	FLOORING					
	Concrete Flooring					
	Providing & laying cement concrete flooring 1:2:4, finished with floating coat of neat cement					
FLO051	20mm aggregates, 40mm thick	2.50	sq.m			
	TILING - WALL & FLOOR					
GL0001	Providing and fixing vitrified tiles in skirting, step risers, dado and wall in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, on 12 mm thick	9.75	sq.m			

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	cement mortar 1:3 (1 cement:3 sand) finished with Tiles grout flush-pointing					
GL0002	Providing and laying vitrified tiles in flooring, treads of steps and landings in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) finished with tiles grout flush pointing	2.50	sq.m			
	ROOFING					
	C.G.I Sheeting					
	Providing & fixing Pre-Painted Galvalume (PPGL) sheeting, including necessary accessories for fixing sheet (excluding the cost of purlins, rafter and trusses) - 25g					
RF0004	25g (0.50mm)	2.50	sq.m			
	PLUMBING - INDOOR WORK					
	Water Supply					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same, including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making the good walls etc.					
PI0317	25 mm nominal outer dia Pipes	5.00	m			
PI0318	32 mm nominal outer dia Pipes	5.00	m			
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	1.00	each			
	Basins & Sinks					
	Providing & fixing white vitreous china wash basin,					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	including C.I brackets, 15mm C.P. brass pillar taps, c.p. chain & rubber plug, 32mm pvc waste, 32mm dia. trap & union, repair walls					
PI0088	Flat back wash basin 550x400mm with single 15mm c.p. brass pillar tap	2.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	2.00	each			
	Bathroom Accessories					
PI0250	Providing & fixing 600x450mm beveled edge mirror (superior glass) incl.4mm A.C sheet base fixed to wooden cleats	1.00	each			
	Providing & fixing toilet paper holder					
PI0263	Recessed ceramic, roll-type, 150 x 150 mm	1.00	each			
	Providing & fixing soap dish					
PI0276	Recessed, ceramic, 150x150 mm	1.00	each			
	PLUMBING - OUTDOOR WORK					
	PVC pipes and Fittings					
	Providing & fixing P.V.C soil waste and vent pipes, single or double socketed, including pipe clip complete (excluding the cost of PVC fittings)					
PO0370	75mm dia	5.00	m			
PO0371	50mm dia	3.00	m			
PO0372	110mm dia	5.00	m			
	Providing & fixing P.V.C Pipe connector					
PO0380	110mm dia	1.00	each			
	Providing & fixing P.V.C plain bend					
PO0405	75mm dia					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

		1.00	each			
PO0406	50mm dia	1.00	each			
PO0407	110mm dia	1.00	each			
	Providing & fixing P.V.C door bend					
PO0415	75mm dia	1.00	each			
PO0417	110mm dia	1.00	each			
	Providing & fixing P.V.C Nahani Trap					
PO0565	110mm inlet & 75mm outlet	1.00	each			
	PLASTERING					
	Cement Plaster					
	Providing & laying 15mm cement plaster on rough side of single or half-brick wall					
PL0031	C.M 1:4	16.25	sq.m			
	Providing & laying 20mm cement plaster					
PL0041	C.M 1:4	16.25	sq.m			
	PAINTING & WALLPAPER					
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	22.75	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	22.75	sq.m			
	PVC Casing Capping (Surface)					
	Supplying and fixing PVC casing & capping on					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	surface including cup washer, screws, bends, elbows, Tees, corners, etc. complete as required					
CD0044	12x12x1.2 mm	5.00	m			
	BOXES					
	PVC Boxes					
BX0021	2 Module	1.00	each			
	Supplying & fixing of PVC boxes for switch/socket outlet/switch socket combined/ gang switches on surface including painting etc as required					
BX0021	2 Module	1.00	each			
	Switches & Sockets on PVC surface box					
	Supplying & fixing of 6A switch on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS121	6A switch SP 2-way	1.00	each			
	Supplying & fixing of socket outlet on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0151	5 pin universal socket outlet	1.00	each			
	Supplying & fixing of prewired indoor surface/ceiling mounted round/square LED luminaires of 3000/4000/6000k, complete with all accessories with necessary testing & commissioning.					
IL0302	5W	1.00	each			
	DISMANTLING TOILET IN LOAN SECTION					
	DISMANTLING & DEMOLITION WORK					
	Brick & Hollow Block Masonry					
	Demolishing brick work including stacking useful					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	materials & disposal of rubbish within 50m lead					
DD0017	In cement mortar	1.52	cu.m			
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave, hold fasts, and stack within 50m lead	1.00	each			
	Cisterns					
	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	1.00	no			
	IN MANAGER QUARTER					
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	550.66	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	550.66	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	550.66	sq.m			
	RAILING WORKS ON RIGHT ELEVATION OF GROUND FLOOR					
	CLEARING AND GRUBBING					
	Clearing Grass					
CG0001	Clearing grass including removal of rubbish within 50m of site	7.73	sq.m			
	EARTH WORK					
	Excavation (Manually)					
	Earth works in surface excavation, depth <300 mm, width > 1.5m, area >10 Sq.m in plan,					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	including disposal of excavated earth within 50m lead & 1.5m lift and disposed soil to be neatly dressed					
EW0021	All types of Soil	7.73	sq.m			
	CONCRETE WORK					
	Plain Cement Concrete					
	Providing and laying in position plain cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. upto floor five level, excluding the cost of centering and shuttering					
CW0024	1:3:6 (1 cement: 3 sands: 6 graded crushed rock 20 mm nominal size)	2.32	cu.m			
	Form work					
	Providing & fixing centering and shuttering (formwork) using Timber, including strutting, propping etc. and removal of formwork - Foundations, Footings and all works upto Plinth Level, etc.					
RC0090	Foundations, Footings, all works upto Plinth Level, etc.	11.17	sq.m			
	STONE/MUD					
	Stone Soling Filling & Edging					
SM0072	Providing and laying Hand packed stone filling or soling with stones	1.16	cu.m			
	STEEL WORK					
	Fabricated & Built - up Sections					
	Steel work welded, in built up sections, trusses, frameworks including cutting, hoisting, fixing and					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	appl. pPrimingcoat of red lead paint					
SW0022	In Tubular sections	391.86	kg			
	PAINTING & WALLPAPER					
	Painting Items					
	Providing and applying finishing coats					
PT0047	Synthetic enamel, for steel & woodwork, two coats for new work	20.06	sq.m			
Total Cost of works in figures:				Nu.		
Total cost of works in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

4. Lot IV: Trashigang Branch Office (Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).

CODE NO.	ITEM NAME	QTY	UNIT	RATE	AMOUNT	REMARKS
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	4.00	each			
AR	Dismantling flooring & wall tiles of any size including stacking of useful materials & disposal of rubbish within 50m lead	28.75	sq.m			
	Cisterns					
DD0100	Dismantling of flushing cistern & European WCP of any size including stacking of useful materials & disposal of rubbish within 50 m lead	4.00	no			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.14	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	5.35	sq.m			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	2.80	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc.					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	complete					
WW0645	250mm	4.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
WW0656	250mm	8.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	8.00	each			
	STEEL					
	Doors / Windows & Accessories					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)as per the manager requirement.					
SW0046	Sliding and open able doors	26.17	kg			
	Extra for providing and fixing plain glass panes on aluminum section complete (excluding the cost of aluminum frame & accessories)					
SW0056	5mm thick, plain glass	5.95	sq.m			
	TILING - WALL & FLOOR					
GL0001	Providing and fixing vitrified tiles in skirting, step risers, dado and wall in different sizes (Sizes and thickness to be specified by the engineer/as per manager recommendation) in all colours and shade, on 12 mm thick cement mortar 1:3 (1 cement:3 sand) finished with Tiles grout flush-pointing	28.75	sq.m			
	PLUMBING - INDOOR WORK					
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	6.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	6.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	6.00	each			
	Flexible Connector for basin					
MR	Supply & installation of flexible stainless steel braided hose pipe connector as per requirement standard size suitable for both hot & cold and includes all fitting labor and sealing materials.	4.00	each			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	303.97	sq.m			
PT0002	Dry oil bound distemper	46.12	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	303.97	sq.m			
PT0011	Metal work - synthetic red oxide primer including surface preparation removing by scrapping and sand papering	46.12	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	303.97	sq.m			
PT0048	High gloss synthetic enamel/for steel & woodwork, two coats on new work	46.12	sq.m			

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	ELECTRICAL WORKS IN BUILDING					
	SWITCHES & SOCKETS					
	Supplying & fixing socket outlet on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0175	3-pin, 6A socket outlet, shuttered	5.00	each			
	INDOOR LUMINIARES					
	Surface Luminaire (Light Emitting Diode Source)					
	Supplying & fixing of prewired indoor surface/ceiling mounted round/square LED luminaires of 3000/4000/6000k, complete with all accessories with necessary testing & commissioning.					
IL0302	5W	5.00	each			
	FANS					
	Supplying, installation, testing & commissioning of ceiling fan 240-volt A.C 1400 rpm with all accessories such as down rod, sweep 3 Nos., canopy 2 Nos., condenser and fan body etc. complete as required					
FN0002	1200mm sweep	2.00	each			
Total cost of works in figures:				Nu.		
Total cost of works in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

5. Lot V: Samdrup Jongkhar Branch Office *(Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).*

CODE NO.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT	REMARKS
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	21.00	each			
AR	Dismantling of old AC and stacking within 50m lead	1.00	each			
	Cisterns					
DD0100	Dismantling of flushing cistern of any size including stacking of useful materials & disposal of rubbish within 50 m lead	6.00	no			
	REINFORCED CONCRETE					
	Concreting Items					
	Providing & laying in position reinforced cement concrete excluding the cost of centering, shuttering and reinforcement - all work upto plinth level					
RC0003	1:2:4 (1 cement: 2 sands: 4 graded crushed rock 20 mm nominal size)	0.11	cu.m			
	Steel Reinforcement					
RC0083	Providing & fixing Thermo-Mechanically Treated reinforcement bar (Yield Strength 500 MPa) for R.C.C work including cutting, bending, binding and placing in position complete	20.74	kg			
	Formwork					
	Providing & fixing centering and shuttering (formwork) using Timber, including strutting, propping etc. and removal of formwork - Foundations, Footings and all works upto Plinth Level, etc.					
RC0090	Foundations, Footings, all works upto Plinth Level, etc	0.01	sq.m			
	WOODWORK					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.23	cu.m			
	Wall and ceiling Linings					
	Providing & fixing frames (wall or ceiling) Class 'A' (conifer) plain lining, tongued and grooved, including necessary fixtures, wooden plugs and priming coat on unexposed surfaces (including cost of frames)					
WW0091	20 mm thick	60.00	sq.m			
	Plywood					
	Providing & fixing Plywood lining with necessary nails etc. including complete beading (excluding cost of frame)					
WW0132	6 mm, commercial	7.50	sq.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	9.84	sq.m			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	4.92	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	6.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
WW0656	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	12.00	each			
	Other fittings					
WW0677	Providing & fixing bright finish brass hydraulic door-closer	2.00	each			

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	uPVC Window (without wire mesh)					
	Providing, fixing and installation of 2-track, UPVC sliding windows including 5mm clear glass with hardware fittings - EPDM gaskets, U- groove roller, Aluminum track, Fastner nut, interlock, touch lock and wool pile, and fixing existing window grills complete.					
WW0718	Plain white window	36.93	sq.m			
	STEEL					
	Fabricated & Built - up Sections					
	Steel work welded, in built up sections, trusses, frameworks including cutting, hoisting, fixing base rollers steel wheels and appl. priming coat of red lead paint including finish paint complete with accessories.					
	For Main Entrance Sliding Gate through Compound wall					
SW0022	In Tubular sections	499.16	kg			
	Doors / Windows & Accessories					
	Providing & fixing in position with vertical channels 20x10x2mm and braced with flat iron, diagonals 20x5mm with top and bottom rails of T-iron 40x40x6mm with 38mm dia steel pulleys complete with bolts, nuts, locking arrangement, stoppers handle including applying a priming coat of red lead paint					
SW0030	Collapsible steel shutters	15.64	sq.m			
	FLOORING					
	Concrete Flooring					
	Providing & laying cement concrete flooring 1:2:4, finished with floating coat of neat cement					
FL0051	20mm aggregates, 40mm thick	140.83	sq.m			
	TILING - WALL & FLOOR					
GL0001	Providing and fixing vitrified tiles in skirting, step risers, dado and wall in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, on 12 mm thick cement mortar 1:3 (1 cement:3 sand) finished with Tiles grout flush-pointing	73.77	sq.m			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

GL0002	Providing and laying vitrified tiles in flooring, treads of steps and landings in different sizes (Sizes and thickness to be specified by the engineer/as per design) in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) finished with tiles grout flush pointing	351.77	sq.m			
	ROOFING					
	C.G.I Sheeting					
	Providing & fixing Pre-Painted Galvalume (PPGL) sheeting, including necessary accessories for fixing sheet (excluding the cost of purlins, rafter and trusses) - 25g					
RF0004	25g (0.50mm)	5.13	sq.m			
	PLUMBING - INDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0300	15 mm nominal outer dia Pipes	12.8	m			
	Storage Tanks					
	Providing & fixing plastic tank including all accessories complete (Brand-Rabten) and a 1 HP water pump with all necessary electrification works.					
PI0032	1000 litre capacity	2.00	each			
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	6.00	each			
	Water Supply Fittings					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	6.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	6.00	each			
	PLUMBING - OUTDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0302	25 mm nominal outer dia Pipes	68.00	m			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	2,342.47	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	2,342.47	sq.m			
	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	2,342.47	sq.m			
	ROAD WORKS					
	Road Marking					
RW0241	Providing and applying permanent road marking on the road surface as per technical specification, (manually)	115.20	sq.m			
	ELECTRICAL WORKS IN BUILDING					
	RE-WIRING					
	PVC Casing Capping (Surface)					
	Supplying and fixing PVC casing & capping on surface including cup washer, screws, bends, elbows, Tees, corners,					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

	etc. complete as required					
CD0048	32x10x1.2mm	163.00	m			
	BOXES					
	PVC Boxes					
BX0021	2 Module	10.00	each			
	Supplying & fixing of PVC boxes for switch/socket outlet/switch socket combined/ gang switches on surface including painting etc as required					
BX0024	6 Module	5.00	each			
	SWITCHES & SOCKETS					
	Switches & Sockets on PVC surface box					
	Supplying & fixing of 6A switch on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS121	6A switch SP 2-way	20.00	each			
	Supplying & fixing of socket outlet on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0151	5 pin universal socket outlet	7.00	each			
	Supplying & fixing of switch/socket on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0166	5/6 pin, 6/16A socket outlet, shuttered	12.00	each			
	INDOOR LUMINAIRES					
	Surface Luminaire (Light Emitting Diode Source)					
	Supplying & fixing of prewired indoor surface/ceiling mounted round/square LED luminaires of 3000/4000/6000/6000k, complete with all accessories with necessary testing & commissioning.					
IL0302	5W	20.00	each			
	WIRING SYSTEM					
	POINT WIRING FOR PVC CASING & CAPPING					
	Wiring for points in excess length above long points with 1.1kV grade, PVC insulated copper conductor cable in PVC casing and capping including connections, painting, testing and commissioning etc. as required					

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

WP0187	2x4 sq.mm	163.00	m			
	SWITCH GEARS, DBs & BUSBAR					
	Miniature Circuit Breaker (MCB)					
	Supply & Installation, testing & commissioning of miniature circuit breaker (MCB) single pole, 230-volt A.C complete with all accessories suitable to fix on a din-bar etc. as required					
GB0270	6A	13.00	each			
GB0272	16A	12.00	each			
	Distribution Board (DB)					
	Supply & fixing of SPN distribution board (DIN type) with metal door, 230-volt A.C complete with all accessories without MCB/isolator/RCCB outgoing or incoming etc. as required					
GB0525	16 ways	2.00	each			
	EARTHING					
	Earthing & Loop Earthing					
	Providing and fixing of earthing including all accessories, machinery enclosure, C.I cover plate having locking arrangement, watering pipe with excavation and refilling work including charcoal or coke, salt and copper strip(25x3mm) from earth plate to main earthing busbar including all accessories, nuts, bolts, lugs, clamps, testing of earth resistance and submission of test results complete as required.					
ET0002	With copper earth plate 600x600x3mm	1.00	each			
Total cost of work in figures:				Nu.		
Total cost of work in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF QUARTER BUILDINGS

1. Lot VI: Mongar Branch Office *(Please total all item costs and submit them as one consolidated quote in the tender.bt online submission).*

CODE NO.	ITEM NAME	QTY	UNIT	RATE	AMOUNT	REMARKS
	DISMANTLING & DEMOLITION WORK					
	Woodwork					
DD0025	Dismantling woodwork of sectional area 40 sq.cm and above in frames, trusses (<10m span) including stacking within 50m lead	0.32	cu.m			
DD0030	Dismantling doors, windows and clerestory windows >3sq.m (steel/wood) including architrave & window grill, shutter, hold fasts, and stacking within 50m lead	87.87	each			
	Cisterns					
DD0100	Dismantling of flushing cistern & European WCP of any size including stacking of useful materials & disposal of rubbish within 50 m lead	4.00	no			
	REINFORCED CONCRETE					
	Providing & laying in position reinforced cement concrete work in suspended floor, roofs having slope upto 15 Degree, landings, balconies, shelves and chajjas upto floor five level excluding the cost of centering, shuttering and reinforcement					
RC0013	1:1:2 (1 cement: 1 sand: 2 graded crushed rock 20 mm nominal size)	0.90	cu.m			
	Steel Reinforcement					
RC0083	Providing & fixing Thermo-Mechanically Treated reinforcement bar (Yield Strength 500 MPa) for R.C.C work including cutting, bending, binding and placing in position complete	222.50	kg			
	Form work					
	Providing & fixing centering and shuttering (formwork) using Shuttering Plywood, including Timber frame and timber strutting, propping with complete form tie system etc. and removal of formwork -					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

RC0113	Suspended floor, roof, landing, shelves and their supports, balconies, chajjas, etc.	6.00	sq.m			
	WOODWORK					
	Dressed Timber Framing					
	Providing & fixing in position dressed woodwork in frames of doors, windows, clerestory windows and other frames, wrought and framed					
WW0001	Class 'A' (conifer)	0.15	cu.m			
	Door & Window Shutters					
	Providing & fixing 35mm thick Paneled or glazed doors and windows Shutters etc. complete including hinges					
WW0210	Class 'A' (conifer)	6.56	sq.m			
	Kicking plate					
WW0630	Providing & fixing anodized aluminum kicking plate, 4mm thick with necessary aluminum screws etc. complete	3.28	sq.m			
	Providing & fixing brass tower bolt (barrel type) with necessary screws etc. complete					
WW0645	250mm	6.00	each			
	Providing & fixing brass sliding door bolt with nuts necessary screws etc. complete					
WW0656	250mm	6.00	each			
	Providing & fixing brass handle with necessary screws etc. complete					
WW0665	150mm	12.00	each			
	STEEL					
	Fabricated & Built - up Sections					
	Steel work welded, in built up sections, trusses, frameworks including cutting, hoisting, fixing					

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	and appl. pPrimingcoat of red lead paint & finishing paint.					
SW0022	In Tubular sections	93.75	kg			
	Doors / Windows & Accessories					
	Providing & fixing anodized Aluminum section for doors, windows, ventilators, partitions framing, false ceiling framing of specified sections including all accessories such as U-rubber gasket for fixing glass panes, weather strips or weather seals, roller, springs, etc complete (excluding the cost of glass panes or boards in case of partitions/doors/windows and ceiling boards in case of ceiling)as per the manager requirement.					
SW0045	Sliding, open, able, and pivoted windows	221.91	kg			
	PLUMBING - INDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0300	15 mm nominal outer dia Pipes	16.80	m			
	Pans & Cisterns					
	Providing & fixing European-type vitreous china w.c pedestal including seat and lid with c.p brass hinges, 15 lit white vitreous china low level cistern, fittings, brackets and repairing walls complete					
PI0050	white, with plastic seat & lid	6.00	each			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Urinals					
	Providing & fixing white vitreous china flat back, lipped front urinal basin 430x260x350mm, including all fittings, painting, and repairing walls complete					
PI0065	One bowl	1.00	each			
	Water Supply Fittings					
	Providing & fixing c.p. brass bibcock					
PI0205	15mm, standard vertical, c.p knob	6.00	each			
	Providing & fixing toilet paper holder					
PI0260	C.P. brass	6.00	each			
	PLUMBING - OUTDOOR WORK					
	CPVC Pipe					
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes - class 1 (SDR11), having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
PI0302	25 mm nominal outer dia Pipes	61.00	m			
	PAINTING & WALLPAPER					
	Surface Preparation					
	Surface preparation removing by scraping, sand papering, including scratch repairs					
PT0001	White colour-wash	1,694.11	sq.m			
	Painting Items					
	Providing & applying one coat of primers					
PT0010	Cement primer	1,694.11	sq.m			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Providing and applying finishing coats					
PT0052	Vinyl plastic emulsion paint, for cement, masonry, plaster, two coats on new work	1,694.11	sq.m			
	ELECTRICAL WORKS IN BUILDING					
	RE-WIRING					
	PVC Casing Capping (Surface)					
	Supplying and fixing PVC casing & capping on surface including cup washer, screws, bends, elbows, Tees, corners, etc. complete as required					
CD0048	32x10x1.2mm	263.00	m			
	BOXES					
	PVC Boxes					
BX0021	2 Module	31.00	each			
	Supplying & fixing of PVC boxes for switch/socket outlet/switch socket combined/gang switches on surface including painting etc as required					
BX0024	6 Module	13.00	each			
	SWITCHES & SOCKETS					
	Switches & Sockets on PVC surface box					
	Supplying & fixing of 6A switch on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS121	6A switch SP 2-way	30.00	each			
	Supplying & fixing of socket outlet on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0151	5 pin universal socket outlet	15.00	each			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

	Supplying & fixing of switch/socket on existing PVC surface box including necessary cutting, connection testing etc. as required.					
SS0166	5/6 pin, 6/16A socket outlet, shuttered	15.00	each			
	Supplying & fixing of prewired indoor surface/ceiling mounted round/square LED luminaires of 3000/4000/6000/6000k, complete with all accessories with necessary testing & commissioning.					
IL0302	5W	23.00	each			
	OUTDOOR LUMINAIRES					
	Street Lighting					
	Supplying, fixing, testing & commissioning pre-wired outdoor LED street light luminaires with 3000/4000/6000K, complete with all accessories.					
OL0410	70W	4.00	each			
	WIRING SYSTEM					
	POINT WIRING FOR PVC CASING & CAPPING					
	Wiring for points in excess length above long points with 1.1kV grade, PVC insulated copper conductor cable in PVC casing and capping including connections, painting, testing and commissioning etc. as required					
WP0187	2x4 sq.mm	217.00	m			
	SWITCH GEARS, DBs & BUSBAR					
	Miniature Circuit Breaker (MCB)					
	Supply & Installation, testing & commissioning of miniature circuit breaker (MCB) single pole, 230-volt A.C complete with all accessories suitable to fix on a din-bar etc. as required					
GB0270	6A	15.00	each			

**RFP FOR RENOVATION & REVAMP WORKS FOR BRANCH OFFICE AND STAFF
QUARTER BUILDINGS**

GB0272	16A	12.00	each			
	Distribution Board (DB)					
	Supply & fixing of SPN distribution board (DIN type) with metal door, 230-volt A.C complete with all accessories without MCB/isolator/RCCB outgoing or incoming etc. as required					
GB0525	16 ways	2.00	each			
	EARTHING					
	Earthing & Loop Earthing					
	Providing and fixing of earthing including all accessories, machinery enclosure, C.I cover plate having locking arrangement, watering pipe with excavation and refilling work including charcoal or coke, salt and copper strip(25x3mm) from earth plate to main earthing busbar including all accessories, nuts, bolts, lugs, clamps, testing of earth resistance and submission of test results completes as required.					
ET0002	With copper earth plate 600x600x3mm	1.00	each			
Total cost of works in figures:				Nu.		
Total Cost of works in words:						

Financials – 100%

Formula to calculate points

Financial = (Lowest quoted Bid/Individual quoted Bid amount) X 100%

NOTE: Please submit your quotes along with the “Bid Submission Form” (Annexure I) above.