

NATURAL RESOURCES DEVELOPMENT CORPORATION LIMITED
BABJIGOENPA SANITATION FOREST ROAD BILL OF QUANTITY

Location: Bjemo, Chabcha, Chukha

Length of road: 340 m

SI no	Description	Qty	Unit	Rate	Amount	Remarks
1.00	EARTH WORKS:					
1.10	Right-of-way-clearing:					
	a) Clearing jungle including up-rooting of vegetation and felling of trees of girth greater than 300mm & stacking within 50m of the site.					
	L(m) B(m)					
	340.00 10.00	3400	m ²			CG0002
1.20	Formation Cutting					
	Excavation of road formation/trace/box cutting in both soil and rock strata using an excavator, including separate stacking of excavated soil, rock, and sandstone materials within 50 meters for reuse. The excavated material shall be transported over a distance of up to 1000 meters, regardless of station markings. All disposed material shall be leveled and neatly dressed. The general formation width shall be 6 meters; however, increased widths shall be adopted at zigs, sharp ridges, and valley sections as instructed by the site supervisor. Cutting width shall be carried out strictly as per the drawings and site instructions.					
	340	340.00	LS			LUMPSUM
2.00	CROSS DRAINAGE WORKS:					
2.10	Log Culverts					
	Complete construction of log culverts as per the drawings, using suitable road alignment timber with diameter not less than 500 mm. The work includes excavation for foundations, placement and alignment of logs as specified in the drawings including royalty if required, and all associated works required to complete the structure in accordance with design and instructions.					
	0	0.00	Nos			NRDCL
2.10	Cross Drains					
	Complete construction of cross drains as per the drawings after every 40m interval, using suitable road alignment timber with diameter not less than 500 mm. The work includes excavation for foundations, placement and alignment of logs as specified in the drawings including royalty if required, and all associated works required to complete the structure in accordance with design and instructions.					
	9	9.00	Nos			NRDCL
3.00	ROAD WORKS:					
3.10	Embankment:					
	Construction of embankment by laying dry earth in horizontal layers not exceeding 150mm in depth (compacted), including watering, power rolling, dressing and preparation of site with selected excavated earth within 500 m lead					

	L(m)	W(m)	H(m)	Nos	Volume					
	340.00	3.00	0.3	1	306	306.00	m ³			RW0030
3.40	Side Drain									
	Earth work in excavation for side drain over areas using Excavator, exceeding 300mm in depth, 1.5m in width as well as 10 sq.m in area on plan, including dressing, levelling and disposal of excavated earth, lead up to 50m and lift up to 1.5m in all types of soil and rock both. The rate shall be applicable for both rock and soil portion.									
	L(m)	W(m)	H(m)	Nos	Volume					
	340.00	1.00	1	1	340	340.00	m ³			RW0049
GRAND TOTAL:										